


# G - 50' Perimeter Incompatibility Buffer



Section G - 50' Type 2 Incompatibility Buffer

Planting for this buffer shall consist of:

- Canopy trees 20' on center.

 A minimum 6' ht. continuous solid opaque visual screen composed of hedges or shrubs, either alone or in combination with a wall, fence and/or berm A wall counts as 1 layer of planting; however, a wall shall require a continuous hedge along both sides of the wall and shall then satisfy the shrub planting requirement in lieu of the following:

- For each 100 linear feet of buffer length the following plants shall be provided:


25 large shrubs (36" ht) spaced 48" oc minimum

25 medium shrubs (24" ht) spaced 30" oc minimum


50 small shrubs (18" ht) spaced 24" oc minimum

200 ground cover (6" ht) plants

## H - 50' Type 2 Incompatibility Buffer



## H.1 - 50' Perimeter Incompatibility Buffer



Section I -75' Perimeter Right of Way Buffer Planting for this buffer shall consist of:

- A minimum 2'ht. continuous opaque visual screen composed of planting alone or in combination with a

- 1 Canopy tree per 25 linear feet.

- For each 100 linear feet of buffer length the following plants shall be provided:


25 large shrubs (36" ht) spaced 48" oc minimum

50 small shrubs (18" ht) spaced 24" oc minimum


200 ground cover (6" ht) plants

MAY MEANDER WITHIN RIGHT OF WAY BUFFER


#### I - 75' Perimeter R/W Buffer Public Civic Pod #7 (180th Ave)



## - 95' Perimeter R/W Buffer Pods C & D (180th Ave)



## J.1 - 80' Perimeter R/W Buffer at Public Civic Pod #1 (180th Ave)



Section J.2 - 25' Type 2 Incompatibility Buffer

Planting for this buffer shall consist of:

- Canopy trees 20' on center.


- A minimum 6' ht. continuous solid opaque visual screen composed of hedges or shrubs, either alone or in combination with a wall, fence and/or berm. A wall counts as 1 layer of planting; however, a wall shall require a continuous hedge alona both sides of the wall and shall then satisfy the shrub planting requirement in lieu of the

following plants shall be provided:

25 large shrubs (36" ht) spaced 48" oc minimum

200 ground cover (6" ht) plants

### J.2 - 25' Type 2 Incompatibility Buffer



Section J.3 - 25' Type 2 Incompatibility Buffer

Planting for this buffer shall consist of:

- Canopy trees 20' on center.

- A minimum 6' ht. continuous solid opaque visual screen composed of hedges or shrubs, either alone or in combination with a wall, fence and/or berm. A wall counts as 1 layer of planting; however, a wall shall require a continuous hedge along both sides of the wall and shall then satisfy the shrub planting requirement in lieu of the following:

- For each 100 linear feet of buffer length the following plants shall be provided:

25 large shrubs (36" ht) spaced 48" oc

25 medium shrubs (24" ht) spaced 30" oc

50 small shrubs (18" ht) spaced 24" oc

# J.3 - 25' Type 2 Incompatibility Buffer<sup>20</sup>

Amendments:

Revisions:

Sheet title:

PRELIMINARY

Regulating Plan

**BEACH** 

Consultants:

Suite 400

CIVIL ENGINEER

Sunrise, FL 33323

Lake Worth, FL 33467

TRAFFIC ENGINEER

Simmons and White

2581 Metrocentre Blvd. Suite

**Urban Design Kilday Studios** 

INDIAN TRAILS

**GROVE - PUD** 

Palm Beach County, Florida

2015-07-15

610 Clematis Street, Suite CU02 West Palm Beach, FL 33401

West Palm Beach, FL 33407 (561) 478-7848

954-753-1730

**SURVEYOR** 

(561) 209-6048

**PLANNERS** 

(561) 366-1100

GLH Engineering, LLC

1600 Sawgrass Corporate Pkwy

Sand and Hills Survey, Inc.

8461 Lake Worth Road, Suite 410

PALM BEAC ASSOCIATES

2015-09-28 Resubmittal

2016-01-25 Resubmittal 2016-02-22 Resubmittal

**Zoning Stamps:** 

Sheet number:

PRP-3